451

BANGALORE DIVISION.

ADVERTISEMENT.

The 10th December 1888.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 22nd December 1888 for restoring the Harur Tank, Registered No. 104, Closepet Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1889.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore between the hours of 11 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Abstract of estimated quantities for restoring Harur Tank, Registered No. 104, Closepet Taluk.

Items of Work.	Per.	Quantity.	Rate. Rs.	A.	P.	Cost.	Total of each.	Grand Total.
Bund.—								
Earthwork, watering and tamping ..	C. Yd.	8,220						
New stone work	,,	2,549						
Old stone work	,,	2,646						
Grade stone including edge and bed slab and fixing.. ..	No.	58						
Guide stone to top width ..	,,	58						
Bench mark stones	,,	2						
R. number stones	,,	1						
Gauge stones ..	,,	1						
Removing shrubs, &c.	Item.	1						
Sluices.—								
Repairs to sluices	,,	1						
Right waste weir.—								
Excavation earth and soft rock ..	C. Yd.	24						
Brick in chunam ..	C. Ft.	1,462						
Stone slabs 6" thick	S. Ft.	164						
Plastering with mortar ..	Sqr.	4·00						
New stone sujicut apron ..	C. Yd.	401						
New stone work to wings ..	,,	124						
Date stone	No.	1						
Left waste weir.—								
Earthwork excavation	C. Yd.	160						
Brick in chunam	C. Ft.	2,404						
Stone slabs 6" thick ..	S. Ft.	702						
Plastering with mortar ..	Sqr.	4·00						
New stone sujicut apron ..	C. Yd.	115						
Old stone work	,,	342						
New stone work to wings ..	,,	48						
Removing bund, &c	Item.	1						
Date stone	No.	1						

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes as earnest money, and be superscribed "Tender for restoring the Harur Tank, Registered No. 104, Closepet Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

R. T. SCALDWELL,
Executive Engineer.